No	Description of item	Unit	No	L	B	D	Qty	Rate	Amount
				Not Operated					
	For Cutting Road Surface								
202	Supplying and fixing of class A (medium duty) GI pipe of wall thickness not less than 3.25mm on pole/wall/drain crossing with necessary clamping arrangements for UG cable of 1.1 KV **P. No. 62 / I No. 7.12.1 KPWD Electrical SR 2014-15**	Mtr							
				Not Operated					
	40mm dia GI pipe								
203	Supplying and fixing L.T. cast Iron pot heads suitable for 1.1 KV class UG cable filled with necessary bitumen/insulating compound complete with terminals, clamps, bolts, nuts and washers etc., **P. No. 62 / I.No. 7.13.2 KPWD Electrical SR 2014-15**	No.							
				Not Operated					
	16Sqmm								
204	Supplying, fixing, wiring, earth electrode for grounding conduits, I.C. cutouts and other equipment's on the meter board using 40mm dia 2.90mm thick GI pipe 2.5 mtr long buried in a pit ... The pit should be filled with equal proportion of salt and charcoal 150mm all-round the pipe to complete depth. The connection from the pipe to the conduit etc., is to be established through GI wire of size as per ISI specification 7.3.3. of IS 732 using 12mm dia bolts, nuts, washers and check nuts etc., the pipe shall have 16 through holes of 122 mm dia, **(P No. 55, I No. 7.1) KPWD Electrical SR 2014-15**	No							
				Not Operated					
205	Supplying & fixing of Porcelain fuse channel with cut out on existing wooden/panel using necessary nuts, bolts and washers.**P No. 44 / I No. 6.7.2 KPWD Electrical SR 2014-15**	No.							
				Not Operated					
	32 Amps								
206	KSRB 13-7.1-4: Providing and fixing in position 50mm nominal bore gun metal non-return valve horizontal type of approved make including cost of all materials, labour and HOM of equipments with all leads complete as per specifications NO KBS 13.2.16 / 13.13 **Page No. 90 Item No. 13.55 / PWD SR 2015-16 50 mm dia**	Nos							
				Not Operated					
207	Providing NP/CP waste unions conforming to ISI specifications and fixing them in position as per directions including cost of materials, fixtures and conveyance to work spot etc., complete. **P. No. 92 / I. No. 13.81.3 PWD SR 2014-15**	No							
				Not Operated					
	50mm dia								

Sl No	Description of item	Unit	No	L	B	D	Qty	Rate	Amount
208	Supplying and fixing 50mm dia GI X nipple with ISI mark with all lead and lift loading unloading and labour charges etc complete **P. XXXVII PWD SR 2015-16**	No							
				Not Operated					
209	Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and 'C' Type curve, indicator ON/OFF, energy cross-3 with Short circuit breaking capacity of 10K and complete wiring as required confirming to IEC 60898. **5-32Amps Group A TPN P No. 47 / I No.6.16.5 KPWD SR 2014-15**	No							
				Not Operated					
210	Fabricating supplying and mounting MS box made out ... SWG suitable for floor / wall mounting, fully weather proof with provision for better heat dissipation, provided with hinged front cover, equipped with tamper proof locking arrangements, with suitable size clamps with necessary cable entry pipe with gland and box should be finished with 2 coats of red oxide primer paint and finally finished with approved colour enameled metal paint etc., complete **P.No. 57, I. No. 6.41.2 KPWD Electrical SR 2014-15**	Sq.Cm							
	16SWG			**Not Operated**					
211	Supplying fully automatic store detta starer unit push button type with suitable wires three contractors one adjustable termal timer mounted on a common base plate held in steel enclosure for use on 400/440 volts 3pase and wired offter fixing to the wooden board for motor upto **12.50 HP (KPWD electrical SR for 2014-15 Page No. 44 Item No. 6.2.1)**	No.							
				Not Operated					

Sl No	Description of item	Unit	No	L	B	D	Qty	Rate	Amount
212	Earthwork excavation for pipeline trenches including deporiting or bank up to a lead of 50 mtrs including shiriry and statting danger lighting and using site rails and boming poles at every 100 mtrs wherever necessary as directed in th following strructure manhole. **Page No. 01/ Item No.1.2.2 / PRED SR 2012-13 Hard Soil**	Cum							
				Not Operated					
213	Providing and installation at site of works P.V.C.Pipes including cost of pipes and specials and incluiding lowring into trenches, laying true to line; level and perfect linking at joints, leak proof including jointing encasing the pipe alround to a depth Not less than 15cm with grave or selected earth avalabile from the execavation Etc., **Page No.15 item No.3.4.2 b PRED SR 2012-13.**	Rmtr							
	75 mm dia 6 KSC PWC pipe			**Not Operated**					
214	Refilling the basement and pipeline treanches with secleted availiable earthe for trench excavation including authority condition in layers from theft including disponsary of the surplus earth with a heavy 200 mtrs **Page No. 3 / Item No. 1.6 / PRED SR 2012-13**	Cum							
	Basic Rate	61.00		**Not Operated**					
215	KSRB 13.6.3-6 : Providing and fixing in position brass gate valve with C.I wheel of approved quality (screwed end) 50mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. Specification No. KBS 13.2.6/13.3 **P. 92 / L13.37 PWD SR - 2015-16**	Each							
				Not Operated					
							TOTAL		**253393.00**

Asst. Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore - 92

	Description of	Unit	No	Length (m)	Breadth (m)	Depth (m)	Quantity	Rate Rs	Amount Rs
E1	KSRB 11-1 : Providing and fixing white vitreous china clay, water closet Indian type (Squatting pan) of size 580mm with footrests, 100mm S or P trap, 10 litre low level, P.V.C flushing cistern (all are approved make) with fittings, C.I / M.S brackets, 32mm diameter flush pipe fittings and clamps, overflow arrangements with specials and 25mm mosquito proof coupling of approved design, painting of fittings and brackets, cutting and making good the wall and floor wherever required, including cost of materials, labour complete as per								
		pan	4				4.00		
						Total Qty	4.00	3975.05	15900.20
E2	Providing and laying plat form using prepolished, water cut / gang saw 40mm thick telephonic Black Granite. laid on existing vertical -supports and fixing in CM 1:3 proportion. Including cutting to required shape, pattern with paper joints, including full rounding for nosing, finished with cement mortar, pointed with colour pigments to match the colour of slab making through jointing with sealant, making holes 25mm x 12mm grooves in joints								
		Sqm	1	1.45	0.6		0.87		
		Sqm	1	4.3	0.6		2.58		
		Sqm	1	1.5	0.6		0.90		
	Deduction								
	Steel Sink	Sqm	10	0.4	0.45		-1.80		
						Total Qty	2.55	3996.59	10191.30
E3	Providing and Fixing Stainless Steel sink of sizes upto 60cms x 45cms in 20mm thick granite slab of by cutting required thickness and width of grooves and fixing using adhesives etc., complete including cost and conveyance of all materials, labour for all items of work, HOM of equipment with all lead and lift, loading and unloading, transportation charges and all other incidental charges etc., complete as per specification and								
		Each	10				10.00		
						Total Qty	10.00	6164.38	61643.80
E4	Cutting granite slab upto 40mm thick and required width of grooves for fixing Stainless Steel sink upto 60cm x 45 cms and fixing using adhesives.								
		Each	10				10.00		
						Total Qty	10.00	1187.07	11870.70
E5	Providing and fixing M.S.Grill over existing compound wall as per Chief Architect drawing No. 12686, using 16mm x 16mm M.S.Square rod at 150mm c/c spacing and 6mm x 40mm M.S. flats at horizontal and 6mm x12mm M.S. flat for ornamental design and providing shop edge design at the vertex of every vertical rods, including welding, grinding wherever necessary. All the steel surface should be thoroughly cleaned free of rust and painted with anti corrosive paint (shop paint) etc., complete. The work includes cost of all materials, labour charges for all items of work, hire charges for welding, cutting and grinding equipment, and electricity charges,								
	Compound Wall								
	EasternSide	Sqm	1	46		0.75	34.50		
	WesternSide	Sqm	1	50.9		0.75	38.18		
	southernside	Sqm	1	19.5		0.75	14.63		

87.31

	Northen side	Sqm	1	31.1		0.75	23.33		
	Deduction								
	Gate	Sqm	-1	3.5		0.75	-2.63		
		Sqm	-1	4.2		0.75	-3.15		
						Total Qty	**104.85**	**6087.29**	**638252.36**
E6	DINING TABLE With Stainless Steel Top Size 6'X1.5'X2.5'. Heavy Fabricated frame With Powder Coating								
		Each	30				30.00		
						Total Qty	**30.00**	**12943.71**	**388311.30**
E7	Dinning Stools With Stainless Steel Plate. Heavy Fabricated Frame with Powder Coating abd SS Plate.								
		Each	100				100.00		
						Total Qty	**100.00**	**1676.78**	**167678.00**
E8	Store Room Storage, Size ,9.3 L X 6.6 HX12" D and 9.3 LX 6.6 H X21" D. Heavy Fabricated frame with powder Coating and 18 mm Ply with Lamination.								
		Each	1				1.00		
						Total Qty	**1.00**	**55607.50**	**55607.50**
E9	Double Burner Stove								
		Each	1				1.00		
						Total Qty	**1.00**	**11977.00**	**11977.00**
E10	Single Burner Stove								
		Each	2				2.00		
						Total Qty	**2.00**	**4448.60**	**8897.20**
E11	Commercial Wet Grinder 0.5HP,5 Litres Machine.								
		Each	1				1.00		
						Total Qty	**1.00**	**35075.50**	**35075.50**
E12	Plastic Chair For Hall Without arms National Brand								
		Each	98				98.00		
						Total Qty	**98.00**	**684.40**	**67071.20**
							TOTAL		**1472476.06**

Asst. Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore - 92